## CHITALDRUG DIVISION.

*Dated 5th January, 1918.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 5th February 1918, for constructing Police Station and Lines at Gadimakunte in Jagalur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Station and Lines at Gadimakunte, Jagalur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, Bangalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing Police Station and Lines at Gadimakunte, Jagalur Taluk, Chitaldrug District.

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| 1 | Earthwork excavation, gravelly soil, for foundation and filling in basement, including watering and tamping. | C. yd. | 194 |
| 2 | Stone in clay foundation and basement ... ... ... | C. ft. | 6,567 |
| 3 | Burnt brick in clay superstructure ... ... ... | " | 4,744 |
| 4 | Burnt brick in chunam superstructure ... ... ... | " | 1,829 |
| 5 | Burnt brick in chunam coping with plastering ... ... | R. ft. | 287 |
| 6 | Burnt stone slabs dressed and fixed ... ... ... | S. ft. | 849 |
| 7 | Teakwood lock-up doors as per plan with iron bars, etc., complete ... | " | 49 |
| 8 | Honney wood battened doors with iron clamps, etc., complete ... ... | " | 616 |
| 9 | Honney wood windows, with iron bars, clamps, etc., complete ... ... | " | 89 |
| 10 | Honney wood ventilators with iron bars and expanded metal, etc., complete ... | " | 11 |
| 11 | Honney wood battened ventilators with iron bars, hooks, hinges, etc., complete | " | 24 |
| 12 | Honney wood work wrought and put up ... ... ... | C. ft. | 164·63 |
| 13 | Roofing with 1st Class Mangalore tiles on teak reepers, etc., complete ... | Sqr. | 36·89 |
| 14 | Ridge tiles set in mortar and cement pointing ... ... ... | R. ft. | 109 |
| 15 | Chunnam borders over roof ... ... ... ... ... | " | 109 |
| 16 | Teakwood ceiling ½" thick for lock-up rooms ... ... ... | S. ft. | 210 |
| 17 | Chunnam plastering ... ... ... ... ... | Sqr. | 122·42 |
| 18 | White and colourwashing two coats ... ... ... ... | " | 123·42 |
| 19 | Honney wood eave board ... ... ... ... ... | R. ft. | 482 |
| 20 | Wood oiling two coats to wood work and ceiling ... ... | Sqr. | 15·68 |
| 21 | Tarring wood work two coats and walls of latrine ... ... ... | " | 5 |
| 22 | Teakwood railing in front of station as per plan, complete ... ... ... | R. ft. | 52 |
| 23 | Flooring with 1st class Mangalore tiles over 3" concrete bed and cement pointing. | Sqr. | 12·50 |
| 24 | Flooring with Cuddappah slabs over 3" concrete bed and cement pointing ... | " | 6·68 |
| 25 | Teakwood gate with iron work, etc., complete ... ... ... | S. ft. | 16 |
| 26 | Silicate painting, two coats ... ... ... ... ... | Sqr. | 23·01 |
| 27 | Constructing V-shaped drain to lead off water including cement pointing ... | R. ft. | 298 |
| 28 | Flooring with gravel including watering and tamping ... ... | C. yd. | 24 |
| 29 | Teakwood finials ... ... ... ... ... | Each | 4 |
| 30 | Teakwood pendents ... ... ... ... ... | " | 8 |
| 31 | Cutting groves and dressing stone pillars ... ... ... | " | 2 |
| 32 | Constructing seats in latrine and fixing drain pipes including cement plastering. | Lump | sum. |
| 33 | Providing chimney over kitchen for smoke escape ... ... | Each | 1 |
| 34 | Constructing cistern in kitchen with burnt stone slabs and cement pointing including plastering to sides, etc., complete. | Lump | sum Re. 1 |
| 35 | Providing pestle and mortar stone ... ... ... ... | Each | 6 |
| 36 | Clearing site and levelling ground ... ... ... ... | Lump | sum Re. 1 |
| 37 | Chunam pointing ... ... ... ... | Sqr. | 3·06 |
| 38 | Providing ½" diameter galvanised iron pipe to drain off water from latrine and kitchen. | Each | 12 |

N. ANANDALWAR,
*Executive Engineer.*

4 D